
# **CONSTRUCTION PLANS PIN OAK STREET ROADWAY REHABILITATION**

**JUNE 2021** 

## PROJECT # MAINT 2021-002



ROADWAY CLASSIFICATION: DESIGN SPEED: ADT:

2 LANE RURAL 25 MPH 100< ADT <1,000

# INDEX OF SHEETS

SHEET NO.	TITLE
01	COVERSHEET
02	GENERAL NOTES
03	SCHEDULE OF VALUES
04	TRAFFIC CONTROL PLAN - PHASE 1
05	TRAFFIC CONTROL PLAN - PHASE 2
06	PAVING PLAN
07	PAVING DETAILS

REVISIO	N BLOCK			
SION DESCRIPTION	AFFECTED SHEETS	DATE	APPROVAL SIGNATURE	APPROVAL DATE

## NOTES:

- 1. THIS PROJECT LIES WITHIN THE CITY LIMITS OF DRIPPING SPRINGS, TEXAS.
- 2. THIS PROJECT LIES WITHIN THE CONTRIBUTING ZONE OF THE EDWARDS AQUIFER.
- 3. NO PORTION OF THIS PROJECT LIES WITHIN ZONE AE AS IDENTIFIED BY THE FEDERAL MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP COMMUNITY PANEL NO.48209C0115F DATED SEPTEMBER 2, 2005 HAYS COUNTY, TEXAS AND INCORPORATED AREAS.
- 4. ROADWAY IMPROVEMENT PLANS WERE PREPARED WITH THE BEST INFORMATION AVAILABLE THROUGH FIELD OBSERVATIONS. PER THE DIRECTIONS OF THE CITY EXISTING TOPOGRAPHIC SURVEY VERIFICATION ANALYSIS WERE NOT PERFORMED AS PART OF THIS PROJECT.
- 5. TRAFFIC COUNTS FOR VEHICLES USING PIN OAK ROAD WERE NOT AVAILABLE TO THE ENGINEER DURING DESIGN. PAVEMENT SECTIONS RECOMMENDED ARE BASED ON AN APPROXIMATION OF EXISTING PAVEMENT SECTIONS OBSERVED IN THE FIELD BY PAVETEX AND DOCUMENTED IN AN EMAIL TO THE CITY ENGINEER DATED APRIL 10, 2019.
- 6. CONTRACTOR IS RESPONSIBLE FOR ANY ADDITIONAL SURVEY VERIFICATION REQUIRED TO COMPLETE THE PROJECT.
- 8. RIGHT-OF-WAY LINES SHOWN HEREON ARE APPROXIMATE.

01 OF 07 GILP-BLK.ctb

#### GENERAL CONSTRUCTION NOTES Α.

- THE CONTRACTOR IS TO CONTACT ONE OF THE FOLLOWING FOR THE LOCATION OF EXISTING FACILITIES AT 1 LEAST 48 HOURS PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION ACTIVITIES:
- TEXAS EXCAVATION SAFETY SYSTEM (TESS) 1-800-245-4545
- TEXAS ONE CALL SYSTEM (TOCS) 1-800-344-8377
- PRIOR TO ANY CONSTRUCTION. THE ENGINEER SHALL CONVENE A PRE-CONSTRUCTION CONFERENCE 2. BETWEEN THE CITY OF WIMBERLY HER/HIMSELE THE CONTRACTOR OTHER LITH ITY COMPANIES ANY AFFECTED PARTIES AND ANY OTHER ENTITY THE CITY OR ENGINEER MAY REQUIRE
- ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE 3 REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION. OSHA STANDARDS MAY BE PURCHASED FROM THE GOVERNMENT PRINTING OFFICE: INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 611 E, 6TH STREET, AUSTIN, TEXAS
- CONTRACTOR SHALL TAKE ALL DUE PRECAUTIONS TO PROTECT EXISTING FACILITIES FROM DAMAGE. ANY DAMAGE INCURRED TO EXISTING FACILITIES AS A RESULT OF CONSTRUCTION OPERATIONS SHALL BE REPAIRED IMMEDIATELY BY THE CONTRACTOR, AT NO ADDITIONAL COST TO OWNER
- CONTRACTOR TO GIVE NOTICE TO ALL AUTHORIZED INSPECTORS, SUPERINTENDENTS OR PERSONS IN CHARGE OF PUBLIC AND PRIVATE UTILITIES AFFECTED BY HIS OPERATIONS AT LEAST 48 HOURS PRIOR TO COMMENCEMENT OF WORK
- CONTRACTOR TO COMPLY WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL REQUIREMENTS REGARDING EXCESS AND WASTE MATERIAL, INCLUDING METHODS OF HANDLING AND DISPOSAL.
- CONTRACTOR TO COORDINATE INTERRUPTIONS OF ALL UTILITIES AND SERVICES. ALL WORK TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE APPLICABLE UTILITY COMPANY OR AGENCY INVOLVED.
- WHEN UN-LOCATED OR INCORRECTLY LOCATED A BREAK IN UTILITY LINES OR OTHER UTILITIES AND 8. SERVICES ARE ENCOUNTERED DURING SITE WORK OPERATIONS. CONTRACTOR SHALL NOTIFY THE APPLICABLE UTILITY COMPANY IMMEDIATELY TO OBTAIN PROCEDURE DIRECTIONS. CONTRACTOR SHALL COOPERATE WITH THE APPLICABLE UTILITY COMPANY IN MAINTAINING ACTIVE SERVICES IN OPERATION.
- WHEN CONSTRUCTION IS BEING CARRIED OUT WITHIN EASEMENTS. THE CONTRACTOR SHALL CONFINE HIS 9. WORK TO WITHIN THE PERMANENT AND TEMPORARY EASEMENTS, PRIOR TO FINAL ACCEPTANCE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL TRASH AND DEBRIS WITHIN THE PERMANENT AND TEMPORARY EASEMENTS. CLEAN-UP SHALL BE TO THE SATISFACTION OF THE CITY
- CONTRACTOR SHALL KEEP ACCURATE RECORDS OF ALL CONSTRUCTION THAT DEVIATES FROM THE 10. PLANS.RECORD SHALL BE KEPT IN AN ONSITE SET OF MARKED-UP RECORD DRAWINGS.
- CONTRACTOR TO LOCATE, PROTECT, AND MAINTAIN BENCHMARKS, MONUMENTS, CONTROL POINTS AND 11. PROJECT ENGINEERING REFERENCE POINTS. RE-ESTABLISH DISTURBED OR DESTROYED ITEMS BY REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, AT NO ADDITIONAL COST TO OWNER.
- 12. CONTRACTOR SHALL STRIP SIX (6) INCHES OF TOPSOIL FROM ALL AREAS SUBJECT TO GRADE MODIFICATION. REMOVE ALL AREAS OF WEAK SOIL.
- 13. THE CONTRACTOR SHALL PROTECT ALL EXISTING FENCES. IN THE EVENT THAT A FENCE MUST BE REMOVED, THE CONTRACTOR SHALL REPLACE SAID FENCE OR PORTION THEREOF WITH THE SAME TYPE OF FENCING TO A QUALITY OF EQUAL OR BETTER THAN THE ORIGINAL FENCE.
- 14. UPON COMPLETION OF THE PROJECT, THE SITE(S) AS DEFINED HEREIN SHALL BE CLEANED OF ALL DEBRIS AND LEFT IN A NEAT AND PRESENTABLE CONDITION.
- 15. ALL ADJOINING PAVEMENT SECTIONS SHALL BE PROTECTED DURING ALL PHASES OF CONSTRUCTION AND ANY DAMAGES INCURRED DUE TO CONTRACTOR'S OPERATION SHALL BE REPAIRED AND/OR REPLACED AT THE CONTRACTOR'S EXPENSE
- CONTRACTOR TO CONTROL DUST CAUSED BY THE WORK AND COMPLY WITH POLLUTION CONTROL 16 REGULATIONS OF GOVERNING AUTHORITIES (NO SEPARATE PAY).
- 17. TRAFFIC CONTROLS TO BE INSTALLED IN ACCORDANCE WITH THE CURRENT TXDOT MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND TXDOT BARRICADE AND CONSTRUCTION STANDARDS.
- 18. RE-VEGETATE ALL DISTURBED AREAS UPON COMPLETION OF THE WORK PER CITY CONSTRUCTION STANDARDS
- CONTRACTOR TO EXERCISE CAUTION DURING CONSTRUCTION NEAR AND AROUND GAS LINES AND POWER 19. LINES.
- 20. ALL WORK IS TO BE PERFORMED BETWEEN THE FOLLOWING
  - HOURS 8:00 A.M. TO 5:00 P.M. MONDAY - FRIDAY

ALL WORK REQUIRING CITY INSPECTION SHALL BE PERFORMED MONDAY THRU FRIDAY. THE CITY RESERVES THE RIGHT TO REQUIRE THE CONTRACTOR TO UNCOVER ALL WORK PERFORMED WITHOUT INSPECTION.

- 21. THE CONTRACTOR SHALL MAKE AN EXAMINATION OF THE PROJECT SITE AND COMPLETELY FAMILIARIZE HIMSELF WITH THE NATURE AND EXTENT OF ANY WORK TO BE ACCOMPLISHED. NO EXTRA COMPENSATION WILL BE ALLOWED FOR ANY WORK MADE NECESSARY BY UNUSUAL CONDITIONS OR OBSTACLES. ENCOUNTERED DURING THE PROGRESS OF THE WORK, WHEN SUCH CONDITIONS OR OBSTACLES ARE READILY APPARENT UPON A VISIT TO THE SITE. IF THERE ARE ANY QUESTIONS OF THIS REGARD OR IF THERE ARE ANY DISCREPANCIES BETWEEN THE PLANS AND ACTUAL SITE CONDITIONS THE CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO THE SUBMISSION OF BIDS.
- IN THOSE CASES WHERE FIXED FEATURES REQUIRE. THE DESIGN SLOPES INDICATED HEREIN AND ON THE 22. CROSS SECTIONS MAY BE MODIFIED IN THE FIELD AS DETERMINED BY THE CITY IF EXISTING CONDITIONS SO REQUIRE

- 23. ACCESS TO RESIDENCES, BUSINESSES, AND DRIVEWAYS ALONG THE PROJECT MUST RECEIVE PRIORITY BY THE CONTRACTOR
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF HIS MATERIALS AND EQUIPMENT FROM 24. THEFT, VANDALISM, ANIMALS, FIRE, ETC. WHILE SAID MATERIALS AND EQUIPMENT ARE ON THE PROJECT, WHETHER STORED OR INSTALLED IN PLACE, UNTIL THE PROJECT HAS BEEN ACCEPTED BY THE CITY.

#### ENVIRONMENTAL NOTES Β.

- THE CONTRACTOR TO INSTALL AND MAINTAIN EROSION/SEDIMENTATION CONTROLS AND TREE/NATURAL 1 AREA PROTECTIVE FENCING PRIOR TO ANY SITE PREPARATION WORK (CLEARING, GRUBBING, GRADING, OR EXCAVATION). CONTRACTOR TO REMOVE EROSION/SEDIMENTATION CONTROLS AT THE COMPLETION OF THE PROJECT AND GRASS RESTORATION
- THE PLACEMENT OF EROSION/SEDIMENTATION CONTROLS TO BE IN ACCORDANCE WITH THE APPROVED 2 EROSION AND SEDIMENTATION CONTROL PLAN. DEVIATIONS FROM THE APPROVED PLAN MUST BE SUBMITTED TO AND APPROVED BY THE OWNER'S REPRESENTATIVE
- ALL DISTURBED AREAS TO BE RESTORED UPON COMPLETION OF CONSTRUCTION. NO SEPARATE PAYMENT 3. WILL BE MADE FOR RE-VEGETATION ACTIVITIES. ALL MATERIALS AND LABOR SHALL BE SUBSIDIARY TO OTHER BID ITEMS
- RESTORATION TO BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 1-1/2 INCHES HIGH WITH 85% COVERAGE, PROVIDED NO BARE SPOTS LARGER THAN 25 SQUARE FEET EXIST
- A MINIMUM OF FOUR (4) INCHES OF NEW OR SALVAGED TOPSOIL TO BE PLACED IN ALL AREAS DISTURBED BY 5. CONSTRUCTION
- THE CONTRACTOR TO SEED, SOD OR HYDROMULCH ALL EXPOSED CUTS AND FILLS UPON COMPLETION OF 6. CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR ALL IRRIGATION WATER REQUIRED TO ESTABLISH GRASS TO THE REQUIRED 85% COVERAGE
- EROSION AND SEDIMENTATION CONTROLS TO BE INSTALLED OR MAINTAINED IN A MANNER WHICH DOES NOT 7. RESULT IN SOIL BUILDUP WITHIN TREE DRIPLINE
- TO AVOID SOIL COMPACTION, CONTRACTOR SHALL NOT ALLOW VEHICULAR TRAFFIC, PARKING, OR STORAGE 8 OF EQUIPMENT OR MATERIALS IN THE TREE DRIPLINE AREAS
- WHERE A FENCE IS CLOSER THAN FOUR (4) FEET TO A TREE TRUNK, PROTECT THE TRUNK WITH STRAPPED-ON PLANKING TO A HEIGHT OF EIGHT (8) FEET (OR TO THE LIMITS OF LOWER BRANCHING) IN ADDITION TO THE FENCING
- 10. TREES TO BE REMOVED IN A MANNER WHICH DOES NOT IMPACT TREES TO BE PRESERVED.
- ANY ROOT EXPOSED BY THE CONSTRUCTION ACTIVITY TO BE PRUNED FLUSH WITH THE SOIL. BACKFILL ROOT 11. AREAS WITH GOOD QUALITY TOPSOIL AS SOON AS POSSIBLE. IF EXPOSED ROOT AREAS ARE NOT BACKFILLED WITHIN TWO DAYS, COVER THEM WITH ORGANIC MATTER IN A MANNER WHICH REDUCES SOIL TEMPERATURE AND MINIMIZES WATER LOSS DUE TO EVAPORATION.
- CONTRACTOR TO PRUNE VEGETATION TO PROVIDE CLEARANCE FOR STRUCTURES, VEHICULAR TRAFFIC, 12. AND EQUIPMENT BEFORE DAMAGE OCCURS (RIPPING OF BRANCHES, ETC.) ALL FINISHED PRUNING TO BE DONE ACCORDING TO RECOGNIZED, APPROVED STANDARDS OF THE INDUSTRY (REFERENCE THE "NATIONAL ARBORIST ASSOCIATION PRUNING STANDARDS FOR SHADE TREES"
- 13. THE CONTRACTOR IS TO INSPECT THE CONTROLS AT WEEKLY INTERVALS AND AFTER EVERY RAINFALL EXCEEDING 1/2 INCH TO VERIEV THAT THEY HAVE NOT BEEN SIGNIFICANTLY DISTURBED, ANY ACCUMULATED SEDIMENT AFTER A SIGNIFICANT RAINFALL TO BE REMOVED AND PLACED IN THE OWNER DESIGNATED SPOIL DISPOSAL

#### C. **EROSION & SEDIMENT CONTROL - SEQUENCE OF CONSTRUCTION:**

- TEMPORARY EROSION AND SEDIMENTATION CONTROLS ARE TO BE INSTALLED AS INDICATED ON THE 1. APPROVED SITE PLAN CONSTRUCTION PLAN AND IN ACCORDANCE WITH THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORMWATER POLILITION PREVENTION PLAN (SWPPP) THAT IS REQUIRED TO BE POSTED ON THE SITE, INSTALL TREE PROTECTION, INITIATE TREE MITIGATION MEASURES AND CONDUCT "PRE - CONSTRUCTION" TREE FERTILIZATION (IF APPLICABLE).
- THE ENVIRONMENTAL PROJECT MANAGER AND/OR SITE SUPERVISOR AND/OR DESIGNATED RESPONSIBLE 2. PARTY, AND THE GENERAL CONTRACTOR WILL FOLLOW THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP) POSTED ON THE SITE. TEMPORARY EROSION AND SEDIMENTATION CONTROLS WILL BE REVISED, IF NEEDED, TO COMPLY WITH CITY INSPECTORS' DIRECTIVES, AND REVISED CONSTRUCTION SCHEDULE RELATIVE TO THE WATER QUALITY PLAN REQUIREMENTS AND THE EROSION PLAN.
- 3 THE TEMPORARY EROSION AND SEDIMENTATION CONTROLS WILL BE INSPECTED AND MAINTAINED IN ACCORDANCE WITH THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP) POSTED ON THE SITE
- BEGIN SITE CLEARING/CONSTRUCTION (OR DEMOLITION) ACTIVITIES.
- PERMANENT WATER QUALITY PONDS OR CONTROLS WILL BE CLEANED OUT AND FILTER MEDIA WILL BE 5. INSTALLED PRIOR TO/CONCURRENTLY WITH RE-VEGETATION OF SITE.
- 6. COMPLETE CONSTRUCTION AND START RE-VEGETATION OF THE SITE AND INSTALLATION OF LANDSCAPING.
- AFTER A FINAL INSPECTION HAS BEEN CONDUCTED BY THE CITY INSPECTOR AND WITH APPROVAL FROM THE CITY INSPECTOR, REMOVE THE TEMPORARY EROSION AND SEDIMENTATION CONTROLS AND COMPLETE ANY NECESSARY FINAL RE-VEGETATION RESULTING FROM REMOVAL OF THE CONTROLS. CONDUCT ANY MAINTENANCE AND REHABILITATION OF THE WATER QUALITY PONDS OR CONTROLS

#### STREET AND DRAINAGE NOTES: D.

- HOURS NOTICE PRIOR TO ANY TESTING
- 2 ON THE PLAN
- 3. ALL R.C.P. SHALL BE MINIMUM CLASS III.

#### Ε. PROJECT NOTES:

1 PER TXDOT SPECIFICATION 305 AND SS3089

ALL TESTING SHALL BE DONE BY AN INDEPENDENT LABORATORY AT THE CITY'S EXPENSE. ANY RETESTING SHALL BE PAID FOR BY THE CONTRACTOR. A CITY INSPECTOR SHALL BE PRESENT DURING ALL TESTS. TESTING SHALL BE COORDINATED WITH THE CITY INSPECTOR AND HE SHALL BE GIVEN A MINIMUM OF 24

DEPTH OF COVER FOR ALL CROSSINGS UNDER PAVEMENT INCLUDING GAS, ELECTRIC, TELEPHONE, CABLE TV, WATER SERVICES, ETC., SHALL BE A MINIMUM OF 30" BELOW SUBGRADE UNLESS OTHERWISE SPECIFIED

ASPHALT TO BE STORED ONSITE AFTER DEMOLITION FOR RECYCLED USE IN THE PROPOSED BASE SECTION

L	I.B.P.L.S. Firm Regist T.B.P.E. Firm Regist T.B.P.E. Firm Regist 9701 BRODIEI AUSTIN, TD PH: 512.22	ration # 1 tration # F ANE #203	-9266	
(	ENGINEER'S SEAL:			
THE D COPY PROT AMEN OR TH SUBJ	RIGHT NOTICE: DESIGNS REPRESENTED RIGHTED AND ARE SUBJ ECTION UNDER 17 U.S.C. DED. UNAUTHORIZED US HE DESIGNS REPRESENT ECT THE INFRINGER TO I CIAL ACTION AS PROVIDE	ECT TO CO §101, ET S E OF THES ED THEREI DAMAGES A	PYRIGHT EQ., AS E PLANS N WILL .ND/OR	
	ISIONS:			
NO.	REVISION		DATE	
NO.	REVISION		DATE	
NO.	REVISION		DATE	
NO.	REVISION		DATE	
		6/02/202		
DAT	E:06	SB		
DAT DES CHE	E:06	SB CWG	1	
DAT DES CHE	E:06	SB	1	
DAT DES CHE	E:06	SB CWG NT-2021	1	
DAT	E:06 SIGNED BY: CKED BY: DJ #:	SB CWG NT-2021	1	
DAT	E:06 GIGNED BY: CKED BY: DJ #:MAI	SB CWG NT-2021	1 -002_	
DAT DES CHE PRC	E: GIGNED BY: CKED BY: DJ #:AI MAI EXAMPLE A STREET: PIN OAK ST ROADW	SB CWG NT-2021	1 -002_	
DAT DES CHE PRC	E: GIGNED BY: CKED BY: DJ #:AI MAI DJ #:AI DJ #:AI DI DA AI DI DA AI D	SB CWG NT-2021	1  -002	

## SCHEDULE OF QUANTITIES:

TXDOT	HAYS CO.			
SPEC NO.	SPEC NO.	ITEM DESCRIPTION	UNITS	QTY
110	1.00	EXCAVATION (ROADWAY) (8IN)	SY	3,033
110	10.00	EXCAVATION (ROADSIDE DITCH)	LF	1,400
164	-	CELL FBR MULCH SEED (PERM)	SY	1,244
247	3.00	FLEXIBLE BASE (6 IN)	SY	3,033
302	5.00	TWO COURSE SURFACE TREATMENT	SY	2,785
305	-	SALV, HAUL & STKPL RCL APH PV (2IN)	SY	2,785
310	4.00	PRIME COAT	SY	3,033
460	2.00	CORRUGATED METAL PIPE (18 IN)	LF	63
460	2.00	CORRUGATED METAL PIPE (24 IN)	LF	25
466	9.00	HEADWALL (DOUBLE BARREL 18 IN)	EA	2
466	9.00	HEADWALL (SINGLE BARREL 24 IN)	EA	2
SS3089	-	EMUL TRTMENT (MX NEW BASE & RCL APH) (8IN)	SY	3,033
502	-	BARRICADES, SIGNS & TRAFFIC HANDLING	LS	1
506	-	TEMP EROSION & SEDIMENTATION CONTROLS	LS	1

## NOTES RELATED TO PAY ITEMS AND SPECIFICATIONS

WHERE BOTH HAYS COUNTY AND TXDOT SPECIFICATIONS ARE NAMED IN THE SCHEDULE OF QUANTITIES ABOVE THE DIRECTION PROVIDED BY THE HAYS COUNTY SPECIFICATIONS SHALL SUPERSEDE WHERE IN CONFLICT WITH THE TXDOT SPECIFICATIONS COUNTY SPECIFICATIONS THE ADDITIONAL INFORMATION PROVIDED BELOW CONFLICTS WITH EITHER THE TXDOT OR HAYS COUNTY SPECIFICATIONS THE INFORMATION BELOW SHALL SUPERSEDE.

#### TXDOT ITEM 110 / HAYS CO. ITEM 1.00 - EXCAVATION (ROADWAY)

ITEM SHALL BE PAID FOR BY SQUARE YARD IN PLACE FOR DEPTH SPECIFIED.

#### TXDOT ITEM 110 / HAYS CO. ITEM 1.00 - EXCAVATION (ROADSIDE DITCH CLEANUP)

ITEM SHALL BE PAID FOR LINEAR FOOT OF ROADSIDE DITCH REPAIRED.

THE INTENT OF THIS WORK ITEMS IS TO REMOVE SILT AND SEDIMENT THAT HAS ACCUMULATED IN THE ROADSIDE DITCH OVER TIME AS WELL AS GRADE DITCH TO DRAIN AND IMPROVE DITCH CAPACITY.

#### TXDOT ITEM 164 CELL FBR MULCH SEED (PERM)

SEED MIXTURE SHALL COMPLY WITH THE PLANTING SEASON ACTIVE AT THE TIME PLANTING WILL OCCUR.

SEED MIXTURE SHALL BE APPLICABLE TO SOIL TYPE WITHIN THE PROJECT LIMITS.

THERE WILL BE NO SEPARATE PAY ITEM FOR TEMPORARY WATER FOR IRRIGATION AND ESTABLISHMENT OF GRASSES. ALL IRRIGATION WATER REQUIRED FOR THE ESTABLISHMENT OF 85% COVER FOR THIS PROJECT SHALL BE SUBSIDIARY TO THIS PAY ITEM.


#### ITEM 460 CORRUGATED METAL PIPE CULVERT


EXCAVATION AND BACKFILL, PIPE BEDDING AND CEMENT STABILIZED BACKFILL SHALL BE SUBSIDIARY TO THE PAY ITEMS FOR CORRUGATED METAL PIPE TXDOT SPEC 460.

## ITEM 506 TEMP EROSION & SEDIMENTATION CONTROLS

NEED FOR EROSION CONTROLS IS ANTICIPATED TO BE LIMITED TO FIBER CONTROL LOGS OR SILT FENCE AS NEEDED AT THE DOWNSTREAM END OF EACH DAILY WORK PHASE AND THEREFORE CONTROLS ARE NOT SHOWN ON THE PLANS. CONTRACTOR SHALL INSTALL EROSION AND SEDIMENTATION CONTROLS AS NEEDED TO PREVENT THE MIGRATION OF SEDIMENT DOWNSTREAM INTO EXISTING STRUCTURES OR ONTO ADJACENT PROPERTIES.

	T. <b>B.P.L.S.</b> F T.B.P.E. F 970'	Firm Regi: 1 BRODIE AUSTIN, T PH: 512.2	stration # 1 stration # I LANE #20 X 78748	0193770 F-9266
		IAD GIL 91800 CENSE	PIN 6 /14	/21
THE D COPY PROT AMEN OR TH SUBJ	RIGHT NOTIO IESIGNS REF RIGHTED AN ECTION UND DED. UNAUT IE DESIGNS I ECT THE INFI IAL ACTION	PRESENTED ID ARE SUB ER 17 U.S.O HORIZED L REPRESEN RINGER TO	DAMAGES /	IN WILL AND/OR
	ISIONS:			
NO.	REVISIO	את		DATE
DAT			6/14/202	1
DES CHE	E: IGNED B CKED B )J #:	BY: Y:	SB	
PRC	JECT:			
	R	OADV	TREE VAY FATIO	
SHE			LE OF TIES	-
		~ -	07	





#### TRAFFIC CONTROL NOTES:


- TRAFFIC CONTROL PLANS SHOWN WITHIN THESE PLANS ARE A MINIMUM REQUIREMENT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY ADDITIONAL SIGNS, BARRICADES, FLAGMEN OR OTHER TRAFFIC CONTROL DEVICES AS NECESSARY FOR THE SAFETY OF THE TRAVELING PUBLIC.
- THE CONTRACTOR SHALL NOTIFY THE CITY PUBLIC WORKS/MAINTENANCE DEPARTMENT WHEN ANY TRAFFIC CONTROL CHANGES ARE TO BE MADE. THE NOTIFICATION MUST BE MADE TWO DAYS PRIOR TO ANY CHANGE.
- ACCESS TO ALL DRIVES AND SIDE ROADS, BOTH PUBLIC AND PRIVATE, ARE TO BE MAINTAINED AT ALL TIMES.
- WORK SHALL BE CONDUCTED SO THAT ALL MACHINERY IS OFF PUBLIC RIGHT-OF-WAY BY SUNSET.
- CONTRACTOR SHALL EMPLOY ALL TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE TEXAS MANUAL OF UNIFORM CONTROL DEVICES FOR STREETS AND HIGHWAYS.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF TRAFFIC CONTROL DEVICES THROUGHOUT ACTIVITIES.


# IMPLEMENT TRAFFIC CONTROL PLAN FOR 30 MPH SPEED LIMIT

# CONTRACTOR TO POSITION FLAGGERS ON ALL ENTRANCES TO THE WORK AREA TO CONTROL ONE-WAY TRAFFIC FLOW

	ILLEPI INGINEERING DO IB.P.L.S. Firm Registration # 1 T.B.P.E. Firm Registration # 1 SP01 BRODIE LANE #202 MINISTRIN, TX 78748 PH: 512.220.8100 INEER'S SEAL: C1A0 GLPH 91800	0193770 -9266
	6/2	/21
THE D COPYI PROTI AMEN OR TH SUBJE	RIGHT NOTICE: ESIGNS REPRESENTED BY THESE I RIGHTED AND ARE SUBJECT TO CO SCTION UNDER 17 U.S.C. \$101, ET S DED. UNAUTHORIZED USE OF THES IE DESIGNS REPRESENTED THEREI ICT THE INFRINGER TO DAMAGES A ILA ACTION AS PROVIDED BY FEDE	PYRIGHT EQ., AS SE PLANS N WILL ND/OR
REV	ISIONS:	
NO.	REVISION	DATE
DAT		1
	IGNED BY: SB	— I
CHE PRO	CKED BY: <u>CWG</u>	-002
	TEXAS	
PRO	JECT:	
	PIN OAK STREE ROADWAY REHABILITATIO	
	ET TITLE: TRAFFIC CONTR PLAN - PHASE	

04 OF 07





## TRAFFIC CONTROL NOTES:


- TRAFFIC CONTROL PLANS SHOWN WITHIN THESE PLANS ARE A MINIMUM REQUIREMENT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY ADDITIONAL SIGNS, BARRICADES, FLAGMEN OR OTHER TRAFFIC CONTROL DEVICES AS NECESSARY FOR THE SAFETY OF THE TRAVELING PUBLIC.
- THE CONTRACTOR SHALL NOTIFY THE CITY PUBLIC WORKS/MAINTENANCE DEPARTMENT WHEN ANY TRAFFIC CONTROL CHANGES ARE TO BE MADE. THE NOTIFICATION MUST BE MADE TWO DAYS PRIOR TO ANY CHANGE.
- ACCESS TO ALL DRIVES AND SIDE ROADS, BOTH PUBLIC AND PRIVATE, ARE TO BE MAINTAINED AT ALL TIMES.
- WORK SHALL BE CONDUCTED SO THAT ALL MACHINERY IS OFF PUBLIC RIGHT-OF-WAY BY SUNSET.
- CONTRACTOR SHALL EMPLOY ALL TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE TEXAS MANUAL OF UNIFORM CONTROL DEVICES FOR STREETS AND HIGHWAYS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF TRAFFIC CONTROL DEVICES THROUGHOUT ACTIVITIES.

# IMPLEMENT TRAFFIC CONTROL PLAN FOR 30 MPH SPEED LIMIT

# CONTRACTOR TO POSITION FLAGGERS ON ALL ENTRANCES TO THE WORK AREA TO CONTROL ONE-WAY TRAFFIC FLOW

T.B.P.L.S. Firm Regist T.B.P.E.S. Firm Regist 9701 BRODIE AUSTIN, 1 PH: 512.2 ENGINEER'S SEAL:	stration <b># F-9266</b> LANE #203 X 78748
CHAD CA	612121
COPYRIGHT NOTICE: THE DESIGNS REPRESENTED COPYRIGHTED AND ARE SUB PROTECTOM UNDER 17 U.S. AMENDED. UNAUTHORIZED I OR THE DESIGNS REPRESEN SUBJECT THE DESIGNS REPRESEN SUBJECT ALE INFRINGER TO JUDICIAL ACTION AS PROVID	SJECT TO COPYRIGHT C. §101, ET SEQ., AS JSE OF THESE PLANS ITED THEREIN WILL DAMAGES AND/OR
REVISIONS:	DATE
DATE: 0	6/02/2021
DESIGNED BY:	
CHECKED BY:	
PROJ #: MA	INT-2021-002
CONTRACTOR	
PROJECT:	
PIN OAK S ROADV REHABILI	VAY
SHEET TITLE: TRAFFIC CI PLAN - PH	

05 OF 07



FULL DEPTH REPAR WITH RECYCLED RSPHALT & TWO-COURSE SURFACE TREATMENT PER SECUENCE OF WORK NOTES & CONSTRUCTION DETAILS

LEGEND   FULL DEPTH REPAIR WITH   RECYCLED BASE AND TWO   COURSE SURFACE TREATMENT   ROW   CULVERT   STREET CENTERLINE   DRAINAGE SWALE	CLACK COLORS
A EXISTING GRADE AT EDGE OF PAVEMENT, MAINTAIN NTOURS & DRAINAGE PATTERNS UNLESS OTHERWISE SETATE ALL DISTURBED AREAS UPON COMPLETION OF THE ATH THE ENVIRONMENTAL NOTES AND SPECIFICATIONS IN UJST TO PROPOSED FINISHED GRADE ALL EXISTING NHOLE COVERS, CLEANOUTS, INLET COVERS AND/OR ANY THE PROJECT AREA. IF APPLICABLE. W-CUT AND/OR ADJUST EXISTING PAVEMENT AS A SMOOTH AND CONTINUOUS TRANSITION GRADE. ENTION IS DIRECTED TO THE FACT THAT BOTH OVERHEAD LITIES EXIST IN THE VICINITY OF THE CONSTRUCTION THON OF UNDERGROUND UTILITIES IS NOT CERTAIN. THE NTACT THE APPROPRIATE AREA UTILITY COMPANIES FOR AST4 49 HOURS PRIOR TO CONSTRUCTION OR K SO AS TO PREVENT ANY DAMAGE OR INTERFERENCE S. L PROTECT ALL AREAS OF THE RIGHT-OF-WAY WHICH ARE TUAL LIMITS OF THE PROPOSED CONSTRUCTION FROM ALL BE EXERCISED TO PREVENT DAMAGE TO TREES, R NATURAL SURROUNDINGS, THE CONTRACTOR, AT HIS RE ANY AREAS DISTURBED AS A RESULT OF THEIR THION AS GOOD AS, OR BETTER THAN, THAT PRESENT IN. KEETING WITH THE CITY ENGINEER AND CONTRACTOR IS Y SITE DISTURBANCE. THES PUBLISHED WITH THESE CONSTRUCTION DOCUMENTS ID IN THE BIDDING PROCESS AND ARE NOT TO BE IRACTORS QUANTITY TAKEOFFS. LI MMEDIATELY NOTIFY THE ENGINEER OF ANY OBSTACLES REVENT THE PROPER CONSTRUCTION OF THE PROJECT. STALL EROSION AND SEDIMENTATION CONTROLS AS IE MIGRATION OF SEDIMENTATION CONTROLS AS IE MIGRATION OF SEDIMENTATION CONTROLS AS IE MIGRATION OF SEDIMENT DOWNSTREAM INTO EXISTING YOTO ADJACENT PROPERTIES.	COPYRIGHT NOTICE: THE DESIGNS REPRESENTED BY THESE PLANS ARE COPYRIGHTED AND ARE SUBJECT TO COPYRIGHT PROTECTION MORENT USE OF THESE PLANS AMENDED. UNAUTHORIZED USE OF THESE PLANS NO. REVISION DARK STREET PROJ #: MAINT-2021-002 FROJECT: PIN OAK STREET PIN OAK STREET ROADWAY REHABILITATION SHEET TITLE: PAVING PLAN 06 OF 07

